

Delmon House, 36 - 38 Church Road, Burgess Hill, West Sussex RH15 9AE. Phone: 01444 415776

Case Study

Hospital Equipment Installation

Project Scope – Hospital Equipment Installation

The project was to offload, move and install hospital equipment into Glasgow Dental Hospital. They were two new sterilisers and four washer disinfectors which then had to be taken to the sterile area, installed and connected to existing services in the sterile services department on the 5th floor.



Installation Solution

The hospital is on Sauchiehall Street in Glasgow and the original plan was to erect a scaffold tower with an access platform to the 5th floor. We would then offload the equipment from a delivery vehicle by crane and the machines would be lifted onto the scaffold tower and placed onto skates for transporting within the building to the Sterile Services Dept. Sauchiehall St is a main shopping thoroughfare in Glasgow and closing part of the road to install the scaffold tower and position the crane would cause great disruption. The police would agree to the closure on a Saturday night (for traffic a quiet time of the week) but warned us that our labour force might increase substantially when the pubs closed

for the night! The method also involved removing a large window and some masonry.

We consulted with the hospital authorities and reviewed other options and agreed a novel solution to the problem.

The lower floors of the hospital are built into a hill so the fifth floor on Sauchiehall Street is a basement when viewed from the small street behind. From that street there is access to a hospital car park on the roof of the lower hospital building. Part of the car park is built over the solid rock behind the hospital but the rest (being the roof of the lower building) would not take the weight of a crane. However, we could offload the equipment from a delivery vehicle standing in the street behind. Then we stood our crane partly in the street and partly on the solid part of the car park. The floor of the car park was cut into using diamond cutting tools to create a plug which was then removed. The equipment was lowered through the opening made by removing the plug into the fifth floor below.

The machines were then transported some on skates and some on pallet trucks to their final positions. They were then bolted to the floor and connected to the relevant services i.e. electricity, water, steam and air. All our waste from packing cases etc. was placed into the skip we had arranged and then removed from the site.

Hospital Equipment Result and Client Benefits

This option was in the first instance more expensive but it has major advantages for future deliveries of equipment. The plug which had been removed was reinstated in such a way that it could be removed again in future for this purpose.

We also avoided a policing problem on busy Sauchiehall Street by thinking outside the box.

If you have a requirement to move or install equipment in a hospital do contact us.